BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGAR ZONE

WORK ORDER SCHEDULE 'B'

Name of Work : Repair and replacing of damaged lighting fitting set at JP park in ward 17.

Name of the Agency: Prema Electrical Enterprises

Sl.No	Qty	Description of Item	Unit	Rates as per Sanctioned estimate		Amount
				In figure	In words	
1		Supplying PVC/GI flexible conduit pipe...mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either end of the pipe terminated completely				
	25	20mm	Mtr	23.00	Rupees Twenty Three Only	575.00
2		Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to table 3 class 5 of IS:8130-1984 and (Virgin) PVC insulation and sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A.				
	230	3C X 2.5Sq.mm	Mtr	81.60	Rupees Eighty One Only Paise Fifty Nine Only	18768.00
3		Supplying and fixing/replacing condenser for ceiling fan/MV/SV/MH and other luminaries.				
	20	upto 4mfd	Each	104.00	Rupees One Hundred and Four Only	2080.00
4		Supply and fixing of ...Watts heavy duty open construction ferromagnetic copper ballast for HPSV/HPMH lamps.				
	15	70Watts	No	1310.00	Rupees One Thousand Three Hundred and Ten Only	19650.00
5		Supplying and fixing MV lamps on existing fitting mounted on tubular pole.				
	25	125Watts	No	191.00	Rupees One Hundred and Ninety One Only	4775.00
6		Supplying and fixing of HPMH lamps on existing fitting mounted on tubular pole Single end				
	20	70 to150Watts	No	912.00	Rupees Nine Hundred and Twelve Only	18240.00
7		Supply and fixing of 230 volts Porcelain holder for MV/SV/MH lamp.				
	10	70-150Watts lamp Holder	No	123.00	Rupees One Hundred and Twenty Three Only	1230.00
8	10	Supplying and fixing/replacement of Round/ Conical/Diamond shaped HDPE Doom suitable for 125/160Watts post top lamp fittings.	No	2403.00	Rupees Two Thousand Four Hundred and Three Only	24030.00
9	20	Supplying and fixing/replacement of Ignitor suitable for 70 to 400Watts SV/MH fittings.	No	523.00	Rupees Five Hundred and Twenty Three Only	10460.00
Total						**99808.00**
Tender Premium: -0.55% below						

I Agree to carry Out this work at **-0.55%** Below the rates notified above as per the directions of Engineer incharge of Work

Contractor

Executive Engineer(Electrical)
Rajarajeshwarinagar zone, BBMP